

CFS Delegated-Design Submittal Checklist

What your delegated engineer needs to keep the schedule — for fabricators, panelizers & GCs

Contract documents

- Architectural drawings (current revision, with reflected ceiling plans where panels interface).
- Structural EOR drawings, including design loads, deflection criteria, and delegated-design notes.
- Project specifications covering cold-formed steel (typically 05 40 00) and any fire-rating requirements.
- Project address and jurisdiction — the sealing state drives code edition and wind/seismic criteria.

Fabrication information

- Panel fabrication system (e.g., FRAMECAD, Howick, hand-framed) and available stud/track profiles and gauges.
- Panel size/shipping constraints and preferred connection methods.
- Required deliverables: per-panel shop files, opening schedules, shear-wall packages, anchor layouts.

Schedule & coordination

- Steel-roll or fabrication start date the engineering must precede.
- Submittal path: who reviews (architect, EOR, AHJ) and expected review cycles.
- Fire-rated assemblies required (e.g., 1-hr demising walls) and whether a rating evaluation is needed.
- MEP coordination points — planned penetrations beat field-notched studs that need engineered repairs.

TCE provides delegated CFS design and engineer-of-record services in 32 jurisdictions — buildable, economical, sealed in your project's state. trillasengineering.com/cfs-delegated-engineering.html

Trillas Consulting Engineers, LLC · 15476 NW 77 Court, Suite 195, Miami Lakes, FL 33016 · 786-542-5474 · info@trillasengineering.com · trillasengineering.com

Licensed in 30 states, D.C. & Puerto Rico. This checklist is general information, not engineering advice for a specific project.